## Procedures for Making a Video (DVD, Jump Drive, etc.) of the Lightning Preventor 2005 Lightning Protection System

- 1. Introduce yourself and state your company name.
- 2. State the project name and address, and confirm time & date by videoing an activated cell phone. Video must clearly show date & time that appears on cell phone display.



- 3. Take a panoramic view of the jobsite before installation.
- 4. Video the driving of ground rods.
- 5. Video the testing of ground rods and test results.
- 6. Video the connecting of the ground rods.
- 7. Video the air terminal and Serial Number.
- 8. Video the mast and manner of mounting of the mast.
- 9. Video the down conductor and any secondary bonding to the down conductor.
- 10. Video the waterline connection.
- 11. Video the structural steel connections.
- 12. Video common ground connection between the lightning protection system and the electrical ground system.
- 13. Take a panoramic view of the building with the installed lightning protection system.
- 14. Video ground test results with the system complete.

## To obtain Certification, forward the following to:

Lightning Preventor of America 11291 Moore Road Springville, New York 14141



- 1. Video
- 2. Ground test results